



Addendum No. 1

To: Interested Parties
From: John E. Van Riper, Project Engineer
Division of Engineering
Date: Monday, September 23, 2019
Project: Stamped Concrete and Landscaping for County Administrative Building

Acknowledge receipt of this **Addendum No. 1** by signing in the space provided below and returning with your Bid.

Failure to sign and return with your bid may subject the Bidder to disqualification. This **Addendum No. 1** forms a part of the Bid Documents and its supplements, and it modifies them as outlined herein.

This **Addendum No. 1** consists of 3 pages, including this page.

I hereby acknowledge receipt of **Addendum No. 1**:

By: _____ Date _____
Signed Name

Typed Name

Title

For (Firm): _____

80 West Baltimore Street | Hagerstown, MD 21740-6003 | P: 240.313.2460 | TDD: 711

WWW.WASHCO-MD.NET

Stamped Concrete and Landscaping for County Administrative Building

Addendum No. 1

Washington County Employee Parking Facility

Date Issued: Monday, September 23, 2019

Quotes Due: Friday, September 27, 2018 4:00 p.m., local time

The following addendum material is hereby made a part of the Bid Documents. Please note the following changes, information, and/or instructions in connection with the proposed work and submit proposals accordingly.



John E. Van Riper, Project Engineer

By Authority of:
Board of County Commissioners
Washington County, Maryland



Scott Hobbs, P.E.
Director – Division of Engineering

Stamped Concrete and Landscaping for County Administrative Building

Addendum No. 1

- Item 1.01 **Question 1: If work starts after 5:00 PM is there a noise ordinance?** The City of Hagerstown lists the daytime hours between 7 AM and 10 PM for the weekdays and between 9 AM and 11 PM on the weekend. If work needs to occur outside of this time, a variance may be reviewed and issued by the City of Hagerstown.
- Item 1.02 **Question 2: Does stamped Concrete need to be sealed?** No, the concrete will not be sealed.
- Item 1.03 **Question 3: Will there be an area set aside for concrete Truck to wash out?** Currently, the gravel lot located at 49 Jonathan Street is a location where the concrete trucks can be washed out.
- Item 1.04 **Question 4: Prints show 4' concrete but bid forms show 5" concrete, which is correct?** The bid item is measured in square feet by length and width with a uniform depth of 5".
- Item 1.05 **Question 5: Do you have specifications on shade and color this effect pricing?** Brick red with brown is the color using a integral mix in color application. Contractor is to provide color samples for County to select final shade prior to construction.