

**PUR-1434 Circuit Court Bullet Resistant Glass**

	<p><b>Mistral Inc. Bethesda, Maryland</b></p>	<p><b>Clear Security Systems West Caldwell, New Jersey</b></p>
<p><b>TOTAL LUMP SUM: DELIVERY/INSTALLATION OF BULLET RESISTANT GLASS AND HARDWARE</b></p>	<p>\$121,891.00</p>	<p>\$69,990.00</p>
<p>REMARKS/EXCEPTIONS:</p>	<p><b>Bid assumes:</b></p> <ol style="list-style-type: none"> <li>Nothing above current false ceiling will require additional costs not included within this bid.</li> <li>Work requirements by the Court's workday schedule will not require unexpected additional costs not already anticipated by this bid.</li> </ol>	<p><b>Demolition of Existing Counter Components:</b></p> <ol style="list-style-type: none"> <li>CSS will dismantle and remove the existing modular counter, desks, and wall unit where the new counter will be installed.</li> <li>Disposal of existing modular furniture is by others.</li> </ol> <p><b>Bullet Resistant Counter Millwork (per attached Plan Document):</b></p> <ol style="list-style-type: none"> <li>One (I) "L" shape millwork counter system with leg #1 approximately 15' 0" long (standard height counter); and leg#2 being approximately 6' 3" long (ADA counter.)</li> <li>The Employee work counter for the entire millwork system will be 34" AFF, which is ADA height compliant.</li> <li>The 15' 0" counter leg will have a 10" high riser section for standard (standing) height transactions.</li> <li>One (1) return counter top and divider panel bisecting the main counter system, approximately 7' 0" long with the divider panel being approximately 24" high.</li> <li>The 6' 3" counter leg will not have a riser section and will remain at ADA height.</li> <li>New half-wall, approximately 15' 6" long x 3' 8"h, connecting the end of the new counter to the rear concrete wall.</li> <li>Millwork counter and the half-high wall are constructed from wood products, UL Level 3 bullet resistant fiberglass panels, and a matching plastic laminate.</li> <li>Millwork will include (5) grommet holes for wire access, knee-walls, toe kicks, riser sections, countertops, riser top, two (2) S.S. RECESSED deal trays, and four (4) wood/plastic laminate vertical support panels on the Employee side of the counter.</li> <li>Millwork knee-walls will contain open wire raceways for power and computer wires. Removable access panels in the kneespace areas for wire raceway are included.</li> <li>Electrical wiring and conduits for power and computer wire are provided and installed by others.</li> <li>Millwork cabinets: three (3) three-drawer cabinets with standard pulls and glides with a plastic laminate finish, and one (I) double door cupboard with pulls, two (2) adjustable shelves, and a plastic laminate finish.</li> <li>New wall will be made up of wood products, UL Level 3 bullet resistant fiberglass paneling, and a plastic laminate finish to match the new millwork counter.</li> </ol>

**PUR-1434 Circuit Court Bullet Resistant Glass**

<p align="center"><b>Mistral Inc. Bethesda, Maryland</b></p>	<p align="center"><b>Clear Security Systems West Caldwell, New Jersey</b></p>
	<p>13. One (1) Half Vision Security Door, complete with aluminum tube frame with UL Level 3 BR fiberglass inserts, UL Level 3 LP-1250 glazing sheet material, plastic laminate finish on lower half of door to match color and height of new half-high wall, heavy duty closer, heavy duty Select hinge, and a Simplex L1000 pushbutton combination lockset with electric strike.</p> <p>14. Complete millwork drawings are included for all finishes, dimensions, and approval</p> <p><b>Bullet Resistant Barrier Glazing:</b></p> <ol style="list-style-type: none"> <li>1. 1 1/4" thick UL Level 3 LP-1250 acrylicpolycarbonate glazing installed onto the new counter system and above the new half wall (a total of approximately 36 linear feet) to a height of 60" (70" above the ADA counter....or 8' 8" A.F.F.)</li> <li>2. Acrylic louvers, 20" high, spanning the top of the BR glazing (approximately 36 linear feet) to the underside of the 10' 5" high ceiling.</li> <li>3. One (1) Bulk Package Exchange Unit, 16"w x 18"h x 18"d, complete with UL Level 3 LP-1250 glazing, two doors with pull knobs, and an interior mechanical interlock device.</li> <li>4. Complete BRG drawings are included for approval.</li> </ol> <p><b>Project Notes:</b></p> <ol style="list-style-type: none"> <li>1. Prevailing Wage pricing is included below.</li> <li>2. All work will take place during off hours including weekend work on consecutive days/night until complete. (start demolition on a Friday night, work through the weekend, and if necessary complete on a Monday night or Tuesday night....4-5 nights for completion.)</li> <li>3. Performance Bond (estimated at \$2,000.00) is included.</li> <li>4. Materials and Labor Bond (estimated at \$2,000.00) is included.</li> <li>5. CSS to perform a site visit prior to the start of fabrication to confirm dimensions and specification requirements.</li> <li>6. Shop drawings to be provided within ten (10) days from the site visit.</li> <li>7. Any electrical work is by others. There is no electrical work included in this pricing.</li> <li>8. Estimated fabrication, delivery and installation is 90-120 days from receiving an order.</li> <li>9. Any materials or labor not specifically described above have not been included in the pricing below.</li> </ol>