



# Washington County

## M A R Y L A N D

### PURCHASING DEPARTMENT DIVISION OF BUDGET & FINANCE

#### PUR-1583 ADDENDUM NO. 3 INVITATION TO BID

#### RUBBLE LANDFILL CLOSURE

**DATE: Thursday, November 10, 2022**

**BIDS DUE: Wednesday, November 16, 2022  
2:00 P.M.(EDT/EST)**

To Bidders:

This Addendum is hereby made a part of the Contract Documents on which all bids will be based and is issued to correct and clarify the original documents.

Please acknowledge receipt of this Addendum at the appropriate space on the Proposal Form. This Addendum consists of two (2) pages.

**NOTE: All Bidders must enter the Washington County Administration Complex through either the front door at the 100 West Washington Street entrance or through the rear entrance (w/blue canopy roof) which is handicap accessible and must use the elevator to access the Purchasing Department to submit their bid and/or to attend the Pre-Bid Conference. Alternate routes are controlled by a door access system. The general public will be subject to wand search and will be required to remove any unauthorized items from the building prior to entry. Prohibited items include but are not limited to: Weapons of any type; Firearms, ammunition and explosive devices; Cutting instruments of any type - including knives, scissors, box cutters, work tools, knitting needles, or anything with a cutting edge, etc.; Pepper spray, mace or any other chemical defense sprays; and Illegal substances.**

**ITEM NO. 1:** Inquiry: What is the Geotech requirement and gradation for cap layer and vegetative layer. 3"minus?, 6"minus?

Response: The lower 9 inches of the vegetative support layer shall have a maximum particle size of 2 inches, as stated in 31 22 25-5, paragraph 2.1 C.1. The top surface of the closure cap subgrade shall be well graded and free of sharp or angular materials that could compromise the geosynthetics placed on top.

**ITEM NO. 2:** Inquiry: How far from site is telephone and power hook to job trailers available?

Response: Depending on the size of the trailer, the trailer can be placed within 200 ft of the power hook-up

**ITEM NO. 3:** Inquiry: Profile on sheet 6 shows 15" pipe and Detail Shows 12" pipe which is preferred?

100 West Washington Street, Room 3200 | Hagerstown, MD 21740-4748 | P: 240.313.2330 | F: 240.313.2331 | TDD: 711

Response: The down chute pipe should be 15" inches in diameter.

**ITEM NO. 4:** Inquiry: Are quantities shown in bid sheets correct?

Response: All quantities are estimated.

**ITEM NO. 5:** Inquiry: There is compaction and proof roll verbiage in contract and spec documents can this be removed as compaction cannot be achieved?

Response: No.

**ITEM NO. 6:** Inquiry: Can there be a separate item added for prep for liner?

Response: Please include the cost for liner prep with the cost for the geomembrane liner.


**ITEM NO. 7:** Inquiry: Can a line item be added for finish grading prep for liner system?

Response: Please include the cost for finish grading prep with excavation and grading.

**ITEM NO. 8:** Inquiry: Will there be a place provided for clear and grub, root mat waste materials on site or will this have to be hauled off to a place that will take landfill materials?

Response: This material can be placed in the stockpile area designated on site as long as it is free and clear of landfill waste but will ultimately need to be hauled off for disposal.

By Authority of:



Rick F. Curry, CPPO  
Director of Purchasing