## PUR-1629 Grinder Pump Packages

<b>PUR-1629 Grinder Pump Packages</b> Awarded to: Aqua Flow Pump & Supply				Aqua Flow Pump & Supply Hagerstown, MD		BT Plumbing Supply, Inc. Finksburg, MD		Rapid HVAC, Inc. Gaithersburg, MD	
Item No.	Item Description	Unit of Measure	Qty	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price
1	Liberty Pumps - Model #D3684LSG202-36-S Preassembled duplex grinder system, with two 2 Hp, 208-230V, 1 Phase Grinder Pumps with a capacity of 50 GPM and pumping heights to 108' TDH, one 36" dia. x 84" high fiberglass basin, one 36" dia. blank fiberglass cover, one AE24H=3 duplex alternating control panel with high level alarm, complete with GR20 guide rail assemblies, guide rail piping ( <u>stainless steel</u> ), check valves and discharge piping (2" side discharge down 36" from the cover).		2	\$7,433.60	\$14,867.20	\$7,648.93	\$15,297.86	\$12,975.20	\$25,950.40
2	Liberty 2484LSG202-36-S Simplex grinder package, completely factory pre-assembled, including 24" dia. x 84" high fiberglass basin with anti-floatation flange, blank fiberglass cover, 2HP grinder pump, single stage, 208-230V, complete with guide rail assembly ( <u>stainless steel</u> ) including check valve and SXH24+3 simplex control panel, 3 floats, with capacities of 50 GPM and heads to 108' TDH (36" discharge depth).	Ea.	8	\$4,090.33	\$32,722.64 *	\$4,206.46	\$33,651.68	\$6,908.44	\$55,267.52
TOTAL LUMP SUM (Item Nos. 1 & 2)				47,589.84 *		48,949.54		81,217.92	

\* Corrected calculations based on unit pricing

## **<u>Remarks / Exceptions</u>:**

Aquaflow Pump & Supply in addition to the bid outlined in this document, Aquaflow Pump & Supply Co. does and will maintain select equipment, and replacement parts as part of our relationship with Washington County, Department of Water Quality.